

PRINTING OF SCHOOL STATIONERY: 2023-24

S NO	ITEM DEMANDED	A/U	DEMAND
1	TC Withdrawal forms (pad of 100 pages)	Pads	5
2	Forms for refund of security (Pad of 100 each)	Pads	5
3	Students attendance registers(50 pages 1 st 04 pages will be on ledger paper)	Nos	20
4	Admission Forms Pad of 100	Pads	7
5	In/Out call record register (as per format) (350 pages)	Nos	1
6	Daily Attendance of students record register (as per format) (250 pages)	Nos	1
7	Expendable Ledger	Nos	5
8	Property Ledger	Nos	5
9	Service Books as per sample	Nos	50
10	Chairman Sanction Register	Nos	2
11	Substitution Register	Nos	1
12	Leave record register Teachers Staff	Nos	1
13	School Letter Pad	Pads	2
14	Students Adm / Withdrawal Register	Nos	1
15	Students I card	Nos	2300
16	Transfer Certificate Issue Record Register (300 Pages)	book	2
17	Cash Book	book	1
18	Petty Cash Register as per Sample (Ledger Pages) (300 Pages)	No	1
19	Students Security Deposit Record Register as per Sample (300 Pages)	Nos	2
20	File Covers in four different colours hard good quality as per printing sample (APS Jammu Cantt with logo)	Pads	500
21	File Covers White as per printing sample (Superior)	Pads	100
22	Students Health cards as per format (superioer quality)	Nos	2500

23	Students Diary (as per sample)	Nos	2300
24	Teachers Diary (as per sample)	Nos	150
25	Monitor Diary (as per sample)	Nos	100
26	HODs Record Register (as per sample)	Nos	10
27	Observations Record Register (as per sample)	Nos	20
28	Clubs Record Register (as per sample)	Nos	20
29	House Record Register (as per sample)	Nos	10
30	CCA Record Register (as per sample)	Nos	4
31	Sports Record Register (as per sample)	Nos	4
32	Students Book Issue / Return Register 200 pages (as per sample)	Nos	2
33	Printing of School Name and Address on White Envelope (Size- 27 x 12 cm)	Nos	200

Note*:- The quotation of complete items will be accepted only. The rates are including GST. The specimens/ samples will be Collected/ seen in the School during School working Hours 01:00 PM to 03:00 PM.

TECHNICAL SPECIFICATION OF IRON BRIDGE

Structural iron work riveted, bolted or welded in built up sections. Beam and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved iron primer all complete as following specification. (Structure 1St Floor walking Plate farm) (2nd floor top roofing only with GI Sheet & MS Pipes)

1. Dismantling of existing iron structure work in built up sections in angles, tees, flats and channels including all gusset plates, bolts, nuts, cutting rivets, welding etc. including dismembering and stacking. Useful iron section shall be used.
(Qty approx 900 kg)
2. MS Built-up Section Work. Providing, Fabricating, Assembling, hoisting, erecting and placing in position MS Built-up section ISMB (I section) 200 x 100 mm main Horizontal Section and Tie and cross members ISMB 100x75 mm shall be fixed 45 cm at an equal distance Cross member (MS built-up section: Rolled section & plates confirming to IS 2062, All member to be connected / welded with 14 mm thick Gusset plate and main I Beam Section hick to be fixed on Top and Bottom with fixed Nut and Bolt (Qty approx = 3700 kg)
3. Supply and fixing 6 mm thick M.S. sheet, with frame and diagonal braces of 60x60x6 mm angle iron, 10 mm M.S. gusset plates at the junctions and corners, all necessary fittings complete, including applying a priming coat of approved steel primer.
(Qty approx = 270 Sq Ft)
4. Iron Railing work in built up tubular 2" thick round, hollow tubes, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.
(Qty approx = 260 Sq Ft)
5. Design and construction work will be the responsibility of the contractor. The Bidder shall be covered on his risk and cost, if the structure fails.
6. Mention complete rate of above mentioned work incl GST in quotations.

TECHNICAL SPECIFICATION OF KOTA STONE

1. Dismantling of old/ broken Kota stone and fixing of new Kota stone at various spot over 20 mm (average) thick base laid over and jointed with grey cement match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) : 25 mm thick. (Qty approx = 800 Sq Ft)
2. Providing and laying in position cement concrete of specified under kota stone flooring: 1:2:4 (1 Cement: 2 coarse sand (zone-III) : 4 graded stone aggregate 40 mm nominal size) thickness 80mm. (Qty approx.= 800 Sq Ft)
3. During Construction or the opening in brick masonry including dismantling in floor or walls by cutting masonry and making good the damages to walls, flooring and jambs complete, to match existing surface i/c disposal of mulba/ rubbish to the nearest dumping ground.
4. Design and construction work will be the responsibility of the contractor. The Bidder shall be covered on his risk and cost, if the structure fails.
5. Rate mentioned in quotation are per Square Feet basis & include GST.